



KEY

BS 5837:2012 Tree Category

A B C U

TAG Tree / Group Reference (by category)

Individual tree (by category)

Tree group/hedge (by category)

Root protection area - RPA (BS5837)

RPA Modified due to site conditions

TREE PROTECTION PLAN - DETAILS

Tree / Hedge Removal

Trees to be removed

Area of trees to be removed

Protected Areas & Tree Protective Barrier/s

Tree protective fence / barrier (See Detail 1)

Tree protective fence / barrier (See Detail 4)

Construction Exclusion Zone - CEZ

All operations inside of Tree Protective Fencing are to be supervised by an appointed Arboriculturist.

Arboricultural Method Statement/s

All AMS areas are to be worked in strict accordance to detailed arboricultural method statements.

Special protection area - AMS- Temporary Ground Protection

Restricted Activity Area - AMS- Informal paths. Details to be agreed.

AMS: a detailed Arboricultural Method Statement to be agreed with the LPA prior to commencement of development

Documents/plans supplied by client for use in this drawing:

Topographical Survey:

- Southwest Land Surveys 1539

Layout:

- 230301 L 02 02 E Illustrative layout

Accompanying documents which must be read in conjunction with this drawing:

- 05141 Tree Survey Rev A 19.5.23
- 05141 AIA 30.5.23

Notes

- All dimensions are in metres, unless otherwise stated.
- The original of this drawing was produced in colour, a monochrome version should therefore not be relied upon.

Client:	Grass Roots Planning
Project:	Tidcombe Hall, Tiverton, Devon.
Title:	Tree Removal & Retention Plan
Date:	29.11.23
Sheet:	1 of 8
Scale:	1:250 @ A1
Drawn:	JG
Checked:	DS
Dwg Ref:	05141.TRRP 29.11.23

ASPECT
TREE CONSULTANCY

Aspect Tree Consultancy Ltd.
Unit F, Kach Business Park
Pottery Road
Bovey Tracey TQ13 9TZ

Tel: 01364 644822
www.fresh-aspect.com